

- 1) 133 gajalu G+1
 - 2) Earth work
 - 3) Mat size 4x4
 - 4) Steel 10mm
 - 5) Size of the column 9x15 inch
 - 6) 10mm rods are used for the mat
 - 7) 4,16mm and 4,12mm is used for the column
 - 8) For the Pleanth beam, 12mm rods are used.
 - 9) Height of the slab is 10 feet.
 - 10) Zindal 550 grade steel will be used.
 - 11) UltraTech cement will be used for slabs and columns.
 - 12) Brickwork
 - 13) The cost of the red brick is Rs 9
 - 14) Door frames are African teak.
 - 15) flush doors.
 - 16) Double coat plastering
 - 17) During Plumbing work, Sudhakar pipes will be used.
 - 18) During waterline work, ashirvadh pipes will be used.
 - 19) A 1000-liter sentic tank on the slab.
 - 20) A 4000-liter water Tank in the ground.
 - 21) plain poliselling.
 - 22) lapam & paint.
 - 23) Asian paint.
 - 24) havells will be used during wiring.
 - 25) Sudhakar pipes will be used for the electrical work.
 - 26) Indian Toilets.
 - 27) first floor and ground floor Granite.
 - 28) per sft Rs 50 cost of the granite.
 - 24) during concrete work for 1 bag of cement, 8 gampas of sand, and 8 gampas of concrete.
 - 25) during plastering for a bag of cement, 18 gampas of sand..
 - 26) during basemate work for 1 bag of cement, 30 gampas of robo sand.
 - 27) Including compound wall.
- Total:43,50,000 (forty-three lakhs fifty thousand)

Contractor Signature

p.nehemiyarao